

AIP SUPPLEMENT - SUOMI / FINLAND

Aeronautical Information Service

www.ais.fi

Fintraffic ANS, PL 157, FI-01531 VANTAA, ais@fintraffic.fi

AIP SUP NR
060 / 2023

AIRAC

WEF
30 JUN 2023

KUOPION LENTOASEMA (EFKU), RAJOITUKSET JA TILAPÄISET JÄRJESTELYT 30.6. - 31.8.2023 - TYÖVAIHE 2

Kuopion lentoasemalla suoritetaan liikennealueiden perusparannustöitä.

1. Aika

30 JUN 2023, 0300 UTC - 31 AUG 2023, 1500 UTC

2. Muut julkaisut

2.1 Kiitotien 15/33C tiedot on julkaistu erillisellä supplementilla.

2.2 Työvaihetta varten on lisäksi julkaistu erillisillä supplementeilla seuraavat **kartat ja menetelmät** ajalle **15.6. - 7.9.2023**:

EFKU AOC RWY 15/33C
EFKU RNAV SID RWY 33C
EFKU RNAV STAR RWY 33C
EFKU RNP RWY 33C

Nämä kartat ja menetelmät on julkaistu AIRAC-jaksoille julkaisuteknisistä syistä.

Käytettävä kiitotie (15/33C tai 15/33) tullaan kertomaan NOTAMilla. Kiitotie 15C/33 ei ole käytössä tämän supplementin voimassaoloaikana.

3. Rajoitukset

Työalue ja muut liikenteeltä suljetut alueet on esitetty sivun 2 piirroksessa.

3.1 Kiitoteiden käytettävyyss

Kiitotie 33 ei ole käytössä.

Työvaiheen aikana on käytössä **kiitotie 33C**.

THR 33 ei ole käytössä.

Työvaiheen aikana on käytössä **THR 33C**.

3.2 Rullaustiet

Seuraavat rullaustiet ovat suljettu liikenteeltä:

- TWY E
- TWY F
- TWY T välillä TWY D ja TWY F

3.3 **EFKU AOC RWY 15/33** ei ole käytössä.

3.4 **Vaikutukset lähtö- ja lähestymismenetelmiin** julkaistaan NOTAMilla.

4. Merkinnät

4.1 Kiitotien liikenteeltä suljettu osuus on merkitty valoras-teilla.

4.2 THR RWY 33C on merkitty kiitotien yli maalatulla val-koisella viivalla.

4.3 Työmaa-alue on merkitty lipuilla, keiloilla ja punaisilla valoilla (R LIL).

KUOPIO AERODROME (EFKU), RESTRICTIONS AND TEMPORARY ARRANGEMENTS FROM 30 JUN TO 31 AUG 2023 - PHASE 2

Renovation works on manoeuvring area will be carried out at Kuopio aerodrome.

1. Period

30 JUN 2023, 0300 UTC - 31 AUG 2023, 1500 UTC

2. Other publications

2.1 The information for runway 15/33C are published in a separate supplement.

2.2 The following additional **charts and procedures** are published in separate supplements for the period of **15 JUN to 07 SEP 2023**:

EFKU AOC RWY 15/33C
EFKU RNAV SID RWY 33C
EFKU RNAV STAR RWY 33C
EFKU RNP RWY 33C

These charts and procedures are published for AIRAC cycles due to technical publication procedures.

The runway in use (15/33C or 15/33) will be published by NOTAM. Runway 15C/33 is not in use during this supplement.

3. Restrictions

The working area and other areas closed to traffic are shown in the sketch on page 2.

3.1 Runway availability

Runway 33 is not in use.

Runway 33C is in use during the working phase.

THR 33 is not in use.

THR 33C is in use during the working phase.

3.2 Taxiways

The following taxiways are closed to traffic:

- TWY E
- TWY F
- TWY T between TWY D and TWY F

3.3 **EFKU AOC RWY 15/33** is not in use.

3.4 **The impact to departure and approach procedures** will be published by NOTAM.

4. Markings

4.1 The closed portion of the runway is marked with lighted aids.

4.2 THR RWY 33C is marked by a white stripe across the runway.

4.3 The working area is equipped with flags, cones and temporary lights (R LIL).

